4-Piece Bathroom — Estimator Hierarchy Summary

How cost codes appear in the estimator (Step 1 & Step 2)

Legend

```
🟢 WHITE  = Always shown, Included in Base Price (green card)
🔵 BLUE   = Yes/No Toggle (blue card)
🟡 YELLOW = Child of BLUE — appears when parent toggled ON
🟠 ORANGE = Dropdown selection
🟩 GREEN  = Number input (per sqft, per each)
```

STEP 1: ROUGH

```
Progress Bar: 50%
```

📁 DEMOLITION CATEGORY

(accordion — default open, shows "1 selected" badge)

🟢 Site Preparation [$300 — Included in Base]

- Create protective walkway from access point to work area
- Protect flooring and adjacent surfaces
- Set up staging area for materials and tools

💡 Tip available

🟢 Demolition [$1,200 — Included in Base]

- Uninstall and set aside agreed-upon items
- Remove toilet
- Remove tub, shower, and surrounds
- Remove double vanity and sinks
- Remove floor tile
- Remove mirror(s) and bathroom accessories

💡 Tip available

🔵 Is there any wall or ceiling tile being removed? [$0 — Branch, NOT exported]

[Toggle OFF by default]

└── 🟩 How many square feet of tile need to be removed? [$24/sqft]

- Remove tile from designated areas
- Dispose of demolition debris off site
- Install drywall where tile was removed
- Tape, mud, and sand new drywall
- Prime new drywall for paint

💡 Tip available

[Enter value] per sqft

📁 PLUMBING CATEGORY

🟢 Plumbing [$4,200 — Included in Base]

- Install and connect toilet in existing location
- Install and connect double sink or vanity in existing location
- Install alcove tub in existing location and connect to main drain
- Install tub faucet and controls in existing location
- Install copper piping for shower head and controls at tub
- Install rough-in valve for standard shower in separate shower
- Install shower drain in existing location and connect to main drain
- Does not include repair or replacement of main drain lines if required

💡 Tip available

🔵 Do you need any additional plumbing work? [$0 — Branch, NOT exported]
[Toggle OFF by default]

└── 🔵 Water Shut Off Valves [$300]

- Install water shut-off valves in accessible location

💡 Tip available

└── 🔵 Change Tub Style (Alcove is included) [$0 — Branch, NOT exported]
[Toggle OFF by default]

└── 🟠 Select tub style:

- Drop In Tub [+$960]
- Freestanding (Soaking) Tub [+$1,920]
- Jetted Tub [+$1,920]

└── 🔵 Relocate Tub [$960]

- Open subfloor to relocate tub drain within 6 feet

💡 Tip available

└── 🔵 Relocate Shower [$960]

- Open subfloor to relocate shower drain within 6 feet

💡 Tip available

└── 🔵 Handheld Shower Wand [$300–$600]

🟠 Select quantity:

- 1 Wand [+$300]
- 2 Wands [+$600]

└── 🔵 Body Sprays [$600–$2,400]

🟠 Select quantity:

- 1 [+$600]

- 2 [+$1,200]
- 3 [+$1,800]
- 4 [+$2,400]

└─ 🔵 Steam Shower [$6,000 – Allowance]
- Install steam generator unit
- Connect water supply
- Install electrical outlet and dedicated circuit

💡 Tip available

└─ 🔵 Relocate Toilet [$1,440]
- Relocate toilet within 6 feet of existing location

💡 Tip available

└─ 🔵 Convert to Wall-Hung Toilet [$2,160]
- Requires wall framing, in-wall carrier system

💡 Tip available

└─ 🔵 Toilet with Built in Bidet (Washlet) [$600]
- Install bidet seat on existing toilet

💡 Tip available

└─ 🔵 Relocate Sink/Vanity [$960]
- Relocate sink plumbing within 6 feet

💡 Tip available

└─ 🔵 Convert Single to Double Vanity [$720]
- Install additional water supply and drain lines

💡 Tip available

└─ 🟠 Wall Mounted Faucets [$480–$960]
- 1 Faucet [+$480]
- 2 Faucets [+$960]

└─ 🔵 Replace Galvanized Pipes (Bathroom Only) [$1,080]
- Remove and replace galvanized piping with copper

💡 Tip available

📁 ELECTRIC CATEGORY

🟢 Electric [$720 — Included in Base]

- Replace vanity light fixture(s) in existing location
- Replace ceiling light fixture in existing location
- Update outlets and switches in bathroom

💡 Tip available

🔵 Do you need any additional electrical work? [$480 — Trip Charge, exported]

[Toggle OFF by default]

└── 🟠 Add new outlets or switch [$360 each]

- 1, 2, 3, 4, 5, 6

└── 🟠 Relocate existing outlets or switches [$240 each]

- 1, 2, 3, 4, 5, 6

└── 🔵 Add recessed lighting [$0 — Branch, NOT exported]

└── 🟠 Install 2" recessed can lights [$360 each]

- 1, 2, 3, 4, 5, 6

└── 🟠 Install 4" recessed can lights [$360 each]

- 1, 2, 3, 4, 5, 6

└── 🟠 Install 6" recessed can lights [$360 each]

- 1, 2, 3, 4, 5, 6

└── 🔵 Add ceiling light fixture with new switch [$600]

- Install new ceiling light and switch

💡 Tip available

└── 🟠 Install sconces instead of vanity light [$240 each]

- 1, 2, 3, 4

└── 🔵 Add Vanity Light with Switch [$600]

- Open walls to run new wiring

💡 Tip available

└── 🔵 Convert One Vanity Light into Two [$600]

- Run new wiring for second vanity light

💡 Tip available

└── 🟠 Install dimmer switches [$90 each]

- 1, 2, 3, 4

└─ 🔵 Install LED mirror [$240]

- Install electrical connection to hardwire LED mirror

💡 Tip available

└─ 🔵 Install heated floors [$2,400]

- Install Schluter Ditra heating system
- Install thermostat

💡 Tip available

📁 HVAC CATEGORY

(upgrade options only — no base item)

🔵 Replace Exhaust Fan [$480]

- Replace existing exhaust fan in existing location

💡 Tip available

🔵 Relocate existing Exhaust Fan [$720]

- Relocate to new location within bathroom

💡 Tip available

🔵 Install New Exhaust Fan [$1,800]

- Install new exhaust fan where one does not exist

💡 Tip available

🔵 Exhaust fan with features [$300]

- Upgrade to include light, Bluetooth, humidity sensor

💡 Tip available

🔵 Relocate HVAC vent [$960]

- Relocate HVAC vent in floor or wall

💡 Tip available

STEP 2: FINISHES

```
Progress Bar: 100%
```

📁 CARPENTRY CATEGORY

(accordion — shows "1 selected" badge)

🟢 Carpentry [$960 — Included in Base]

- Install vanity in existing location
- Install stock MDF baseboard/trim

💡 Tip available

🔵 Additional Carpentry Items [$0 — Branch, NOT exported]

[Toggle OFF by default]

└── 🔵 Floating Vanity [$360]

- Open wall to install proper backing support

💡 Tip available

└── 🔵 Recessed Mirror(s) [$360]

- Open wall and modify framing

💡 Tip available

└── 🟩 Crown Molding [$30/LF]

- Install stock MDF crown molding
- Includes painting of new molding

[Enter linear footage] per LF

└── 🔵 Replace Bathroom Door [$0 — Branch, NOT exported]

└── 🔵 Swing Door to Swing Door [$720]

- Remove existing swing door and frame
- Install new prehung swing door

💡 Tip available

└── 🔵 Swing Door to Pocket Door [$720]

- Remove existing swing door
- Reframe wall for pocket door system

💡 Tip available

└── 🔵 Pocket Door to Swing Door [$720]

- Remove existing pocket door frame
- Install new prehung swing door

💡 Tip available

📁 TILE CATEGORY

🟢 Tile Install [$6,000 — Included in Base]

- Install Schluter shower system (pre-sloped pan, Kerdi membrane, Schluter drain)
- Apply RedGard waterproofing at tub walls
- Install ceramic/porcelain tile on floor, shower floor, shower walls, tub surround
- Install grout on all new tile

💡 Tip available

🔵 Specialty Tile Options [$0 — Branch, NOT exported]

[Toggle OFF by default]

└── 🟩 Install additional tile in areas not included above [$30/sqft]

- Enter total square footage of additional areas

💡 Tip available

└── 🟩 Tile Sizes [$12/sqft]

- Non-standard tile sizes (outside 3x6 to 12x24)

💡 Tip available

└── 🟩 Tile Material [$18/sqft]

- Natural stone, travertine, granite, handmade tiles

💡 Tip available

└── 🟩 Tile Patterns [$30/sqft]

- Herringbone, chevron, mosaics, custom layouts

💡 Tip available

└── 🟩 Tile Baseboards [$18/LF]

- Install tile baseboards along perimeter

💡 Tip available

└── 🔵 Niche/Ledge [$360]

- Reframe wall studs for shower niche or ledge

💡 Tip available

└── 🔵 Bench [$360]

- Reframe wall studs for shower bench

💡 Tip available

📁 PAINT CATEGORY

🟢 Patch and Paint [$600 — Included in Base]

- Patch minor drywall imperfections
- Caulk new baseboards
- Apply two coats of paint to walls, ceiling, and trim

💡 Tip available

🔵 Paint Options [$0 — Branch, NOT exported]

[Toggle OFF by default]

└── 🟠 Multiple Colors [$90 each additional color]

- 2, 3, 4 colors

└── 🔵 Wallpaper Install [$960 — Allowance]

- Measure, cut, and install wallpaper

💡 Tip available

└── 🔵 Refinish Vanity [$0 — Branch, NOT exported]

└── 🔵 Refinish Single Vanity [$720]

- Surface prep, sanding, priming, new finish

💡 Tip available

└── 🔵 Refinish Double Vanity [$960]

- Surface prep, sanding, priming, new finish

💡 Tip available

📁 ACCESSORIES CATEGORY

🟢 Accessories [$300 — Included in Base]

- Install towel bar, toilet paper holder, and robe hooks

💡 Tip available

📁 SHOWER GLASS CATEGORY

🔵 Door and Panel [$0 — Branch]
[Toggle OFF by default]
└── 🔵 Door and Panel [$2,100]
- 1/2" clear glass, standard 60"x80"
- Hardware finish selectable

💡 Tip available

└── 🔵 Low Iron (ultra-clear glass) [+$672]
- Less green tint, more vibrant colors

💡 Tip available

└── 🔵 Towel Bar [$216]
- Install towel bar on shower glass door

💡 Tip available

🔵 Sliding Door [$0 — Branch]
[Toggle OFF by default]
└── 🔵 Sliding Door [$2,700]
- 3/8" Serenity sliding glass, standard 60"x80"

💡 Tip available

└── 🔵 Bypass System [+$240]
- Two sliding panels bypass system

💡 Tip available

└── 🔵 Low Iron [+$672]

💡 Tip available

└── 🔵 Towel Bar [$216]

💡 Tip available

🔵 Stationary Panel [$0 — Branch]
[Toggle OFF by default]
└── 🔵 Stationary Panel [$1,440]
- 1/2" stationary glass, ~30" wide

💡 Tip available

└── 🔵 Low Iron [+$336]

💡 Tip available

```
└── 🔵 Towel Bar                                    [$216]
        💡 Tip available
```

BASE PRICE SUMMARY (4-Piece)

Category	Item	Client Price
Demolition	Site Preparation	$300
Demolition	Demolition	$1,200
Plumbing	Plumbing	$4,200
Electric	Electric	$720
Carpentry	Carpentry	$960
Tile	Tile Install	$6,000
Paint	Patch and Paint	$600
Accessories	Accessories	$300
TOTAL BASE PRICE		**$14,280**

> All upgrade selections are added on top of this base price.
> Final price shown in floating Price Summary card and Preview page.